

REGIONAL PERFORMANCE MEASURES
SYSTEM PERFORMANCE REPORT

2023

DRAFT

PREPARED BY:



OCTOBER 2023

T23-0X

REPORT DOCUMENTATION

TITLE

Regional Performance Measures – System Performance Report 2023

AUTHOR/PROJECT MANAGER

Keith M. Nichols, PE

ABSTRACT

The Moving Ahead for Progress in the 21st Century (MAP-21) surface transportation legislation established a performance-and outcome-based program. As part of this program, current legislation requires that States and Metropolitan Planning Organizations (MPOs) prepare and use a set of federally-established performance measures that are tied to the national performance goals. Each MPO must set regional targets in the areas of roadway safety, transit asset management, transit safety, pavement condition, bridge condition, roadway performance, and freight.

Setting HRTPO targets is a collaborative effort. The Transportation Technical Advisory Committee (TTAC) recommends targets for the HRTPO Board to consider. In order to assist the TTAC, the committee formed a Regional Performance Measures Working Group. This Working Group includes staff from localities, transit agencies, VDOT, and subject-matter experts.

This Regional Performance Measures – System Performance Report includes a description of the methodology used to calculate each measure, historical data trends for each of the areas, information on statewide targets, a description of the targets that have been established by the HRTPO, and the progress being made towards meeting the established targets. This report is updated on an annual basis to reflect updated targets as well as progress towards meeting the established targets.

REPORT DATE

October 2023

ORGANIZATION CONTACT INFORMATION

Hampton Roads Transportation Planning Organization
723 Woodlake Drive
Chesapeake, Virginia 23320
(757) 420-8300
<http://www.hrtpo.org>

ACKNOWLEDGMENTS

Prepared in cooperation with the U.S. Department of Transportation (USDOT), Federal Highway Administration (FHWA), and Virginia Department of Transportation (VDOT). The contents of this report reflect the views of the Hampton Roads Transportation Planning Organization (HRTPO). The HRTPO is responsible for the facts and the accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the FHWA, VDOT or Hampton Roads Planning District Commission. This report does not constitute a standard, specification, or regulation. FHWA or VDOT acceptance of this report as evidence of fulfillment of the objectives of this planning study does not constitute endorsement/approval of the need for any recommended improvements nor does it constitute approval of their location and design or a commitment to fund any such improvements. Additional project level environmental impact assessments and/or studies of alternatives may be necessary.

NON-DISCRIMINATION

The HRTPO assures that no person shall, on the ground of race, color, national origin, handicap, sex, age, or income status as provided by Title VI of the Civil Rights Act of 1964 and subsequent authorities, be excluded from participation in, be denied the benefits of, or be otherwise subject to discrimination under any program or activity. The HRTPO Title VI Plan provides this assurance, information about HRTPO responsibilities, and a Discrimination Complaint Form.

TABLE OF CONTENTS



| | |
|-----------------------------------|-----------|
| INTRODUCTION | 1 |
| ROADWAY SAFETY | 5 |
| BRIDGE CONDITION | 10 |
| PAVEMENT CONDITION | 15 |
| TRANSIT ASSET MANAGEMENT | 20 |
| TRANSIT SAFETY | 26 |
| ROADWAY PERFORMANCE | 33 |
| FREIGHT | 39 |
| SUMMARY | 43 |
| STATE PERFORMANCE MEASURES | 47 |

INTRODUCTION

The Moving Ahead for Progress in the 21st Century (MAP-21) surface transportation legislation established a performance- and outcome-based program. The Federal Highway Administration (FHWA) defines performance-based planning and programming as a system-level, data-driven process to identify strategies and investments.

A key feature of MAP-21 (and continued under the current federal legislation) is the establishment of national performance goals in the following areas:

- ▶ **Safety** - To achieve a significant reduction in traffic fatalities and serious injuries on all public roads.
- ▶ **Infrastructure Condition** - To maintain the highway infrastructure asset system in a state of good repair.
- ▶ **Congestion Reduction** - To achieve a significant reduction in congestion on the National Highway System.
- ▶ **System Reliability** - To improve the efficiency of the surface transportation system.
- ▶ **Freight Movement and Economic Vitality** - To improve the national freight network, strengthen the ability of rural communities to access national and international trade markets, and support regional economic development.
- ▶ **Environmental Sustainability** - To enhance the performance of the transportation system while protecting and enhancing the natural environment.
- ▶ **Reduced Project Delivery Delays** - To reduce project costs, promote jobs and the economy, and expedite the movement of people and goods by accelerating project completion through eliminating delays in the project development and delivery process, including reducing regulatory burdens and improving agencies' work practices.

As part of this program, federal legislation requires that States and Metropolitan Planning Organizations (MPOs) prepare and use a set of federally-established performance measures that are tied to the national performance goals, as described below.

MEASURES

States and MPOs must prepare and set targets for the federally-established performance measures in the following table:

| Area | Measures |
|---------------------|---|
| Safety | Fatalities |
| | Fatality Rate |
| | Serious Injuries |
| | Serious Injury Rate |
| | Bike/Pedestrian Fatalities & Serious Injuries |
| Transit | Transit Asset Management |
| | Transit Safety |
| Bridge Condition | NHS Bridge Deck Area in Good Condition |
| | NHS Bridge Deck Area in Poor Condition |
| Pavement Condition | Interstate System Pavement in Good Condition |
| | Interstate System Pavement in Poor Condition |
| | Non-Interstate NHS Pavement in Good Condition |
| | Non-Interstate NHS Pavement in Poor Condition |
| Roadway Performance | Interstate Travel Time Reliability |
| | Non-Interstate NHS Travel Time Reliability |
| Freight | Truck Travel Time Reliability |
| CMAQ | N/A for attainment areas (Hampton Roads is in attainment of the national ambient air quality standards for all criteria pollutants specified by EPA.) |

NHS = National Highway System

INTRODUCTION

TARGET SETTING PROCESS

Each MPO must set targets for each of the measures shown on the previous page. These performance measures and targets must be reported based on the MPO's Metropolitan Planning Area (MPA). The Hampton Roads MPA (shown to the right) is comprised of 15 localities including all of Chesapeake, Hampton, Isle of Wight County, James City County, Newport News, Norfolk, Poquoson, Portsmouth, Suffolk, Virginia Beach, Williamsburg, and York County, and portions of Franklin, Gloucester County, and Southampton County.

For target setting, the MPO may:

- ▶ Adopt the statewide targets, but report metrics specific to the MPA
- ▶ Select unique, MPO specific targets, and report metrics specific to the MPA
- ▶ Use a combination of statewide and unique targets

For roadway safety, transit asset management, and transit safety, targets are established for a one-year time horizon and must be set on an annual basis. For bridge condition, pavement condition, roadway performance and freight measures, MPO targets are established for a four-year time horizon, whereas states must establish both two-year and four-year targets. States may adjust their four-year targets at the midway point after two years. If the state elects to make an adjustment and the MPO adopted the statewide targets, the MPO has the option to adopt the adjusted statewide target or to commit to a new, unique MPO-specific target within 180 days.

HAMPTON ROADS METROPOLITAN PLANNING AREA



INTRODUCTION

If an MPO establishes its own unique four-year targets, the MPO may adjust its target at the midway point in a manner that is collectively developed, documented, and mutually agreed upon by the State DOT and MPO. This is allowable regardless of whether the state adjusted its four-year targets or not.

There are no “penalties” for MPOs for not meeting their performance targets, although it can be addressed during the MPO’s quadrennial certification review to ensure adequate performance-based planning efforts.

Setting HRTPO targets is a collaborative effort. The Transportation Technical Advisory Committee (TTAC) – which is comprised of staff from Hampton Roads localities and stakeholders – recommends targets for the HRTPO Board to consider. In order to assist the TTAC, the committee formed a Regional Performance Measures and Targets Working Group. This group includes staff from localities, transit agencies, VDOT, and subject-matter experts.

The HRTPO Board established initial targets throughout 2018. Subsequent annual safety and transit asset management targets were established by the Board during the winter of each year between 2019 and 2023. In addition to safety and transit asset management targets, transit safety targets were approved by the Board in 2021, 2022 and 2023.

INCORPORATING TARGETS INTO THE PLANNING PROCESS

Federal legislation also requires that MPOs include these performance measures and targets and report on progress in planning documents such as the Long-Range Transportation Plan (LRTP) and Transportation Improvement Program (TIP).

The LRTP is a comprehensive and multimodal transportation blueprint that identifies and plans for critically important transportation improvements that not only meet the transportation goals of the HRTPO but also impact the region’s economic vitality and every citizen’s quality of life. The LRTP – which must encompass a minimum of a 20-year time horizon – contains a list of transportation projects that are expected to be constructed based on the anticipated funding available during the time horizon. The Hampton Roads 2045 Long-Range Transportation Plan was approved by the HRTPO Board in July 2021 and work is currently underway on the 2050 LRTP.

The LRTP is required to include a description of the federally-mandated performance measures and targets used in assessing the performance of the transportation system. The LRTP shall also include a system performance report evaluating the condition and performance of the transportation system including progress achieved by the MPO towards meeting the performance targets, and this annual System Performance Report was created to satisfy this requirement. Also, MPOs that elect to conduct scenario planning (as HRTPO did for the 2045 LRTP and will also do for the 2050 LRTP) shall describe how the preferred scenario will improve the performance of the system.

INTRODUCTION

Transportation Improvement Programs are federally-mandated, regional documents that identify the programming of transportation funds over a four-year period. It lists all projects for which federal funds are anticipated, along with non-federally funded projects that are determined to be regionally significant. For performance measures and targets, TIPs shall include a description of the anticipated effect of the TIP toward achieving the performance targets identified by the MPO. The TIP must also link investment priorities to the achievement of performance targets in the plans. The FY 2021-2024 TIP was adopted by the HRTPO Board in May 2020 and work is underway on the FY 2024-2027 TIP.

The HRTPO TIP and LRTP have been updated to include information on the program's impact on each of these areas. Amendments have been made to the TIP each year for updates to safety and transit targets and was amended in 2019 and 2023 for all of the other target areas. The 2040 LRTP was updated via an administrative modification in 2018 and 2020 to account for these regional targets. The 2045 LRTP also includes information on all of the updated measures and targets.

In addition, the metropolitan transportation planning agreement between the MPO, the State, and regional public transportation providers (commonly referred to as the 3-C agreement) was updated in September 2018 to include an article on Performance-Based Metropolitan Planning Process responsibilities. The updated agreement – which details each party's responsibilities in terms of performance-based planning – is available at

<https://www.hrtpo.org/uploads/docs/Signed%20HRTPO%20MPA.pdf>.

WEBSITE

In addition to this document, the HRTPO also maintains a Regional Performance Measures and Targets website. This site includes information on each of these performance measures as well as the basis for selecting each regional target. Progress toward meeting targets is also detailed on the site. The HRTPO Regional Performance Measures and Targets website is <https://www.hrtpo.org/page/regional-performance-measures-and-targets>.



The screenshot shows the Hampton Roads TPO website with a blue header. The header includes the logo 'the heartbeat of HAMPTON ROADS TPO TRANSPORTATION PLANNING ORGANIZATION', a search bar, and links for 'Agendas and Minutes' and 'File Library'. Below the header, a breadcrumb navigation shows 'Home > Transportation > Performance Management > Regional Performance Measures and Targets'. There are social media sharing icons for Facebook, Twitter, LinkedIn, and YouTube. The main content area has a blue header 'Transportation'. On the left, a sidebar lists 'Active Transportation', 'Active Transportation Subcommittee', 'Active Transportation Funding Programs', 'Active Transportation in Hampton Roads Today', 'Active Transportation in the News', 'Active Transportation Projects', 'Birthplace of America Trail', 'HRTPO Regional Active Transportation Planning', 'Linking Hampton Roads: A Regional Active Transportation Plan', 'Local Active Transportation Planning', 'Air Quality', 'Congestion Management', and 'Military Transportation Needs'. The main content area has a section titled 'Regional Performance Measures and Targets' with a sub-section 'Performance Measures'. It describes MAP-21 and the establishment of national performance goals. It lists performance measures: Roadway Safety, Pavement Condition, Bridge Condition, Roadway Performance, Freight Movement, Transit Asset Management and Safety, and On-road mobile source emissions and traffic congestion for CMAQ Program. It also describes the HRTPO staff's role in setting regional performance targets. At the bottom, there is a thumbnail for the 'REGIONAL PERFORMANCE MEASURES SYSTEM PERFORMANCE REPORT 2021'.

ROADWAY SAFETY

MEASURES

- ▶ **Number of Fatalities**
- ▶ **Fatality Rate**
- ▶ **Number of Serious Injuries**
- ▶ **Serious Injury Rate**
- ▶ **Number of Non-Motorized Fatalities & Serious Injuries Combined**

METHODOLOGY

This measure examines the safety of the regional roadway system in terms of the total number and rate of fatalities and serious injuries. In addition, bicyclist and pedestrian (non-motorized) fatalities and serious injuries are analyzed. These measures and targets cover all public roadways regardless of ownership or functional classification and help support the Highway Safety Improvement Program (HSIP), which is a federal program that aims to achieve a significant reduction in traffic fatalities and serious injuries on all public roads.

The number of fatalities throughout the Metropolitan Planning Area (MPA) must be determined on an annual basis using data from USDOT's Fatality Analysis Reporting System (FARS) database. The FARS database contains a description and more than 100 coded data elements of each reported fatal crash throughout the country. A crash must involve a motor vehicle traveling on a roadway that is generally open to the public and must result in the death of a person (either an occupant of a vehicle or a non-motorist) within 30 days of the crash to be included in the FARS database.

In order to determine the annual number of serious injuries within the MPA, data collected and prepared by VDOT is used. Serious injuries are generally defined as incapacitating injuries that can include skull fractures, internal injuries, broken or distorted limbs, unconsciousness, severe lacerations, severe burns, and other injuries that render the person unable to leave the scene without assistance. Law enforcement frequently uses the "KABCO" scale for classifying injuries resulting from crashes, and fatalities and serious injuries are defined as the "K" and "A" on this KABCO scale. (The other classifications in the KABCO scale include "B" for minor but visible injuries, "C" for nonvisible injuries, and "O" for other crashes that do not include an injury.)

In addition to the total number of fatalities and serious injuries in each region, MPOs must measure and establish targets in the rate of fatalities and serious injuries. This rate is based on the number of fatalities and serious injuries that occur per 100 million vehicle-miles of travel (VMT).


Finally, there is a fifth roadway safety measure related to the safety of non-motorists. MPOs must measure and set targets for the annual number of bicyclist and pedestrian fatalities and serious injuries within the MPA. This combined number is produced using FARS data for non-motorized fatalities and VDOT data for non-motorized serious injuries. The number should include all pedestrians, bicyclists, other cyclists, and persons on personal conveyances killed or seriously injured throughout the region in the calendar year.

ROADWAY SAFETY

CURRENT/HISTORICAL CONDITIONS

The following chart shows the number of fatalities, serious injuries, and the combined bike and pedestrian crashes and serious injuries in Hampton Roads between 2008 and 2021. This was the data that was used to assist with determining the regional 2023 targets.

FATALITIES, SERIOUS INJURIES, AND BIKE/PEDESTRIAN FATALITIES & SERIOUS INJURIES IN HAMPTON ROADS (2008-2021)



STATEWIDE 2023 TARGETS

| | |
|---|-------|
| ▶ Number of Fatalities | 1,012 |
| ▶ Fatality Rate per 100M VMT | 1.216 |
| ▶ Number of Serious Injuries | 7,465 |
| ▶ Serious Injury Rate per 100M VMT | 8.971 |
| ▶ Number of Combined Bicyclist & Pedestrian Fatalities & Serious Injuries | 662 |

The statewide 2018 safety targets established by the Commonwealth Transportation board (CTB) were based on the targets included in the [Virginia Strategic Highway Safety Plan](#). These targets included a 2% annual decrease in fatalities, 5% decrease in serious injuries, and a 4% decrease in the number of bicyclist and pedestrian fatalities and serious injuries combined.

A different methodology was used to determine the 2019 statewide targets. Rather than using percent reduction targets, the state based their 2019 targets on annual trend lines to account for the reality that the number of fatalities throughout Virginia was increasing and the number of serious injuries was no longer decreasing.

The 2020 - 2023 statewide targets were also determined using a different methodology. These statewide targets were based on predictive models that take into account a number of external factors related to the amount of roadway travel, economic influences, and changing driver behavior. These model predictions were adjusted to account for the anticipated reduction in crashes due to the completion of roadway safety and capacity projects.

ROADWAY SAFETY


HRTPO 2023 TARGETS

HRTPO has established one-year roadway safety targets each year since 2018. The most recent one-year (2023) roadway safety targets that the HRTPO has established are shown below.


Each of these safety targets is based on the Vision Zero concept, where the number of fatalities, serious injuries, and non-motorized fatalities and serious injuries is reduced by a set amount each year to reach a goal of zero by 2050, the horizon of the upcoming regional Long-Range Transportation Plan. A 0.77% annual increase in vehicle-miles of travel was assumed for the fatality and serious injury rates, which is equal to the rate assumed in statewide targets. More information on the Vision Zero concept is available at <https://visionzeronetwork.org>.

| | |
|--|--------------|
| ▶ Number of Fatalities | 136 |
| ▶ Fatality Rate (per 100 MVMT) | 0.917 |
| ▶ Number of Serious Injuries | 1,513 |
| ▶ Serious Injury Rate (per 100 MVMT) | 10.21 |
| ▶ Number of Non-Motorized Fatalities and Serious Injuries Combined | 177 |

NUMBER OF FATALITIES



FATALITY RATE PER 100 MILLION VEHICLE-MILES OF TRAVEL (VMT)



ROADWAY SAFETY

PROGRESS TOWARDS ACHIEVING TARGETS

HRTPO has established one-year safety targets each year between 2018 and 2023. Each of these one-year regional targets is shown below. Information on whether Hampton Roads achieved its 2021 safety targets based on the 2021 data is also detailed for each of the five safety measures below:

► Number of Fatalities

Targets – 102 ('18), 137 ('19), 124 ('20), **123 ('21)**, 125 ('22), 136 ('23)

MISSING TARGET

There were 176 fatalities in Hampton Roads in 2021, which is significantly higher than the HRTPO's established target of 123. This level of fatalities would also miss the targets set for 2022 and 2023.

► Fatality Rate (per 100 million VMT)

Targets – 0.69 ('18), 0.93 ('19), 0.84 ('20), **0.82 ('21)**, 0.85 ('22), 0.92 ('23)

MISSING TARGET

The fatality rate in Hampton Roads was 1.21 in 2021, which exceeds the HRTPO's established target of 0.82 fatalities per 100 million VMT. This rate would also exceed the targets established for 2022 and 2023.

NUMBER OF SERIOUS INJURIES



SERIOUS INJURY RATE PER 100 MILLION VEHICLE-MILES OF TRAVEL (VMT)



ROADWAY SAFETY

PROGRESS TOWARDS ACHIEVING TARGETS (continued)

► Number of Serious Injuries

Targets – 1,522 ('18), 1,522 ('19), 1,448 ('20), **1,433 ('21)**, 1,498 ('22), 1,513 ('23)

MISSING TARGET

There were 1,772 serious injuries in Hampton Roads in 2021, which is above the HRTPO's established target of 1,433. This number of serious injuries also exceeds the targets established for 2022 and 2023.

► Serious Injury Rate (per 100 million VMT)

Targets – 10.39 ('18), 10.32 ('19), 9.85 ('20), **9.61 ('21)**, 10.19 ('22), 10.21 ('23)

MISSING TARGET

The serious injury rate in Hampton Roads was 12.14 in 2021, which is above the HRTPO's established target of 9.61 serious injuries per 100 million VMT. This rate also exceeds the targets established for 2022 and 2023.


► Number of Non-Motorized Fatalities and Serious Injuries

Targets – 193 ('18), 194 ('19), 163 ('20), **175 ('21)**, 179 ('22), 177 ('23)

MISSING TARGET

There were 203 non-motorized fatalities and serious injuries combined in Hampton Roads in 2021, which exceeds the HRTPO's established target for 2021 of 175. This number of fatalities and serious injuries would also miss the targets established for the years 2022 and 2023.

NUMBER OF NON-MOTORIZED FATALITIES AND SERIOUS INJURIES COMBINED



In order to improve roadway safety, VDOT has undertaken systemic improvements throughout the state such as installing rumble strips and reflective signal backplates, and DMV has allocated additional funding for educational and enforcement safety improvements. In addition, additional funding in the Infrastructure Investment and Jobs Act (IIJA) will be available in Virginia for roadway safety improvements over a five-year period.

In addition, HRTPO is currently in the process of updating the **Hampton Roads Regional Safety Study**, which details regional safety trends, crash characteristics, crash locations, efforts to improve roadway safety, general crash countermeasures, and an in-depth analysis of high crash locations.

BRIDGE CONDITION

MEASURES

- ▶ **Percentage of National Highway System (NHS) Bridge Deck Area in Good Condition**
- ▶ **Percentage of National Highway System (NHS) Bridge Deck Area in Poor Condition**

METHODOLOGY

This measure examines the condition of bridges on the National Highway System (NHS) – including on- and off-ramps connected to the NHS – on a regional basis. In order to be included, each bridge must meet National Bridge Inventory (NBI) standards. These standards include:

- The structure must be located on roadways open to the general public. Bridges located within the security perimeter of military bases and other secure federal facilities are not included.
- The bridge must carry a roadway. Structures that carry only railroad or pedestrian traffic are not included.
- The bridge must be more than 20 feet in length. Culverts are included, as long as the opening in the culvert is more than 20 feet in length.

Bridges are inspected on a regular basis. During these inspections, bridge inspectors rate the condition of the bridge's deck (the driving surface), superstructure (the structural members such as beams and girders), and substructure (the piers, abutments, piles, footings, and other components of the bridge's foundation).

Each of these three components is rated by the bridge inspector from 0 to 9, with 9 representing a component in excellent condition and 0 representing a failed condition or a closed bridge. For culverts, a single rating is given in place of the deck, superstructure, and substructure ratings to assess the general condition of the entire culvert.

Bridges are classified as being in good, fair, or poor condition based on **the lowest of the condition ratings** of the bridge's deck, superstructure, and substructure. For culverts, the classification is based on the culvert condition rating. These classification thresholds are shown in the table below.

| Condition Rating Thresholds for Classification | | | | | |
|--|------|---|--------|------|-----|
| NBI Rating Scale (from 0 – 9) | 9 | 8 | 7 | 6 | 5 |
| | Good | | | Fair | |
| Deck (Item 58) | ≥ 7 | | 5 or 6 | | ≤ 4 |
| Superstructure (Item 59) | ≥ 7 | | 5 or 6 | | ≤ 4 |
| Substructure (Item 60) | ≥ 7 | | 5 or 6 | | ≤ 4 |
| Culvert (Item 62) | ≥ 7 | | 5 or 6 | | ≤ 4 |

BRIDGE CONDITION


For example, if a structure has a deck condition rated as a 7, a superstructure condition rated as a 4, and a substructure condition rated as a 5, then the structure is classified as being in poor condition based on the lowest condition rating of 4.

After each NBI bridge on the NHS is classified as being in good, fair, or poor condition, the deck area of each bridge is calculated by multiplying the full width of the bridge by the bridge's length. The total deck area of each good bridge, fair bridge, and poor bridge throughout the region is summed together, and then divided by the total deck area of all NBI bridges on the NHS in the entire region. This produces a total regional percentage of bridges that are in good condition, fair condition, and poor condition. The regional percentages of NBI bridge deck area in good and poor condition on the NHS are tracked for regional targets.

CURRENT/HISTORICAL CONDITIONS

The following chart shows the percentage of NHS Bridge Deck Area in Good, Fair, and Poor condition in Hampton Roads and throughout Virginia for the years 2017 through 2021:

**PERCENTAGE OF NHS BRIDGE DECK AREA
IN HAMPTON ROADS AND VIRGINIA
BY CONDITION (2017 - 2021)**




BRIDGE CONDITION

STATEWIDE 4-YEAR TARGETS (2021-2025)

- ▶ Percentage of NHS Bridge Deck Area in Good Condition > 25.1%
- ▶ Percentage of NHS Bridge Deck Area in Poor Condition < 3.6%

The statewide four-year targets established by the Commonwealth Transportation Board (CTB) are based on VDOT projections of bridge conditions assuming continued optimal use of maintenance funds. These statewide projections produced by VDOT are shown in the figures to the right.

STATEWIDE PROJECTED PERCENTAGE OF BRIDGES IN GOOD/FAIR CONDITION




BRIDGE CONDITION

HRTPO 4-YEAR TARGETS (2021-2025)


The HRTPO established four-year targets of greater than 25.1% of NHS Bridge Deck Area being in Good Condition, and less than 3.6% of NHS Bridge Deck Area being in Poor Condition. **Both of the percentage of NHS bridge deck area targets match the statewide targets established by the CTB.** HRTPO chose to match the regional bridge condition targets with the statewide targets since the existing condition of bridges in Hampton Roads was similar to the statewide conditions.

- ▶ Percentage of NHS Bridge Deck Area in Good Condition > 25.1%
- ▶ Percentage of NHS Bridge Deck Area in Poor Condition < 3.6%

PERCENTAGE OF NHS BRIDGE DECK AREA IN HAMPTON ROADS IN GOOD CONDITION



PERCENTAGE OF NHS BRIDGE DECK AREA IN HAMPTON ROADS IN POOR CONDITION



BRIDGE CONDITION

PROGRESS TOWARDS ACHIEVING TARGETS

Hampton Roads missed the 2021 targets in both bridge condition measures. More details on each of the two bridge condition measures is shown below:

► **Percentage of NHS Bridge Deck Area in Good Condition**

MISSING TARGET

At 24.8%, this is below the 27% level that was established as the original 2021 target. For 2025, the new regional target has been set at 25.1%.

► **Percentage of NHS Bridge Deck Area in Poor Condition**

MISSING TARGET

At 4.8%, this is above the 3% level that was established as the original 2021 target. For 2025, the new regional target has been set at 3.6%.

In order to improve the condition of bridges throughout the state, VDOT and the CTB have modified the investment strategy for a more balanced approach. VDOT is allocating more funding to rehabilitating bridges before they degrade into poor condition, and a Special Structures fund was created to fund maintenance for major bridges such as the bridge-tunnels in the region. This fund will assist with replacing the existing bridges at the Hampton Roads Bridge-Tunnel, which is currently in poor condition. In addition, additional funding in the IIJA (approximately \$536 million) will be available in Virginia for bridge repair and replacement over a five-year period.

PAVEMENT CONDITION

MEASURES

- ▶ **Percentage of Interstate System Pavement in Good Condition**
- ▶ **Percentage of Interstate System Pavement in Poor Condition**
- ▶ **Percentage of Non-Interstate NHS Pavement in Good Condition**
- ▶ **Percentage of Non-Interstate NHS Pavement in Poor Condition**

METHODOLOGY

This measure examines the condition of roadway pavement on the National Highway System (NHS). The percentage of the region's Interstate system and Non-Interstate NHS pavement in both good and poor condition is analyzed. This measure only includes through travel lanes; ramps, shoulders, turn lanes, crossovers, etc. are not included in this analysis.

Pavement condition data is collected annually by VDOT on every mile of the NHS throughout the state, regardless of roadway ownership. In the Hampton Roads Metropolitan Planning Area (MPA), there are over 500 miles (and over 2,400 lane-miles) of roadway included on the NHS.

Information on VDOT's pavement data collection process is available at http://www.virginiadot.org/info/state_of_the_pavement.asp.

The following metrics are used in determining the pavement condition of each NHS roadway:

- International Roughness Index (IRI) – IRI is used to determine the ride quality based on the smoothness of pavement. It is measured in inches per mile of roadway.
- Rutting and Faulting – Rutting is a surface depression in the wheel path of asphalt roadways, and faulting is the difference in elevation across joints or cracks in jointed concrete.
- Cracking – Cracking measures the percentage of roadway surface area where cracks are present.
- Present Serviceability Rating (PSR) – If the posted speed limit is less than 40 mph, the PSR can be used in place of the metrics above to determine the condition of the pavement.

Each of these aspects of each NHS roadway segment's pavement is rated as good, fair, or poor. These ratings are assigned based on the table below.

| | Good | Fair | Poor |
|-------------------|-----------|---|--|
| IRI (inches/mile) | <95 | 95-170 | >170 |
| Rutting (inches) | <0.20 | 0.20-0.40 | >0.40 |
| Faulting (inches) | <0.10 | 0.10-0.15 | >0.15 |
| Cracking (%) | <5 | 5-20 (asphalt) 5-15 (JCP) 5-10 (CRCP) | >20 (asphalt) >15 (JCP) >10 (CRCP) |
| PSR | PSR ≥ 4.0 | 2.0 ≤ PSR ≤ 4.0 | PSR ≤ 2.0 |

PAVEMENT CONDITION

For roadways with a posted speed limit below 40 mph, the PSR can be used for determining the overall condition of the pavement. Otherwise, the overall condition of each section of NHS roadway is determined based on the pavement type and the appropriate metrics described previously. As shown in the figure to the right, for a section to be in good condition, all of the appropriate metrics must be rated as good. Roadway sections are determined to be in poor condition if two of the three metrics (IRI, cracking, and rutting/faulting) are rated poor for asphalt and jointed concrete, or both metrics (IRI and cracking) are rated poor for continuous concrete.

On a statewide level, no more than 5% of the Interstate system can be in poor condition. If this minimum threshold is not met, the state is required to obligate a specified percentage of its National Highway Performance Program (NHPP) and Surface Transportation Program (STP) funds to improve Interstate pavement condition. There is no similar penalty for the Non-Interstate NHS.


| Overall Section Condition Rating | Pavement Type | | Measures |
|----------------------------------|---|-------------------------------------|--|
| | Asphalt and Jointed Concrete | Continuous Concrete | |
| Good | 3 metric ratings (IRI, cracking and rutting/faulting) | 2 metric ratings (IRI and cracking) | → percentage of lane-miles in "Good" condition |
| Poor | All three metrics rated "Good" | Both metrics rated "Good" | → percentage of lane-miles in "Poor" condition |
| Fair | ≥ 2 metrics rated "Poor" | Both metrics rated "Poor" | |
| | All other combinations | All other combinations | |

PAVEMENT CONDITION

CURRENT/HISTORICAL CONDITIONS

The following charts show the percentage of Interstate and Non-Interstate NHS pavement in good, fair, and poor condition in Hampton Roads and throughout Virginia for the years 2017 through 2021.

PERCENTAGE OF PAVEMENT IN HAMPTON ROADS AND VIRGINIA BY CONDITION INTERSTATE (2017 - 2021)




STATEWIDE 4-YEAR TARGETS (2021-2025)

- ▶ Percentage of Interstate System Pavement in Good Condition > 45%
- ▶ Percentage of Interstate System Pavement in Poor Condition < 3%
- ▶ Percentage of Non-Interstate NHS Pavement in Good Condition > 25%
- ▶ Percentage of Non-Interstate NHS Pavement in Poor Condition < 5%

The statewide four-year targets established by the Commonwealth Transportation Board (CTB) are based on VDOT projections of pavement conditions assuming optimal use of maintenance funds.

PERCENTAGE OF PAVEMENT IN HAMPTON ROADS AND VIRGINIA BY CONDITION NON-INTERSTATE NHS (2017 - 2021)



PAVEMENT CONDITION


HRTPO 4-YEAR TARGETS (2021-2025)

The HRTPO established four-year targets of greater than 45% of Interstate pavement condition being in good condition, less than 3% of Interstate pavement condition being in poor condition, greater than 14% of Non-Interstate NHS pavement condition being in good condition, and less than 5% of Non-Interstate NHS pavement condition being in poor condition.


All of these percentages match the statewide targets established by the CTB, except for the percentage of Non-Interstate NHS pavement in good condition. HRTPO chose to match the regional Interstate targets with the statewide targets since the existing condition of Interstate pavement in Hampton Roads was similar to the statewide conditions. For Non-Interstate NHS, HRTPO chose a regional target for pavement in good condition that was lower than the statewide target, since the amount of the Non-Interstate NHS pavement in good condition is currently well below statewide levels.

- ▶ Percentage of Interstate System pavement in Good Condition **> 45%**
- ▶ Percentage of Interstate System pavement in Poor Condition **< 3%**
- ▶ Percentage of Non-Interstate NHS pavement in Good Condition **> 14%**
- ▶ Percentage of Non-Interstate NHS pavement in Poor Condition **< 5%**

PERCENTAGE OF PAVEMENT IN HAMPTON ROADS IN GOOD CONDITION - INTERSTATE



PERCENTAGE OF PAVEMENT IN HAMPTON ROADS IN POOR CONDITION - INTERSTATE



PAVEMENT CONDITION

PROGRESS TOWARDS ACHIEVING TARGETS

Hampton Roads exceeded the 2021 targets in most of the four pavement condition measures. More details on each of the four pavement condition measures is shown below:

► Percentage of Interstate System Pavement in Good Condition

SURPASSING TARGET

At 51%, this is surpassing (above) the 45% level that was established as the original 2021 target. For 2025, the new regional target remains at 45%.

► Percentage of Interstate System Pavement in Poor Condition

SURPASSING TARGET

At 0.4%, this is surpassing (below) the 3% level that was established as the original 2021 target. For 2025, the new regional target remains at 3%.

► Percentage of Non-Interstate NHS Pavement in Good Condition

MISSING TARGET


At 14%, this is below the 25% level that was established as the original 2021 target. For 2025, the new regional target has been set at 14%.

► Percentage of Non-Interstate NHS Pavement in Poor Condition


SURPASSING TARGET

At 2.1%, this is surpassing (below) the 5% level that was established as the original 2021 target. For 2025, the new regional target remains at 5%.

PERCENTAGE OF PAVEMENT IN HAMPTON ROADS IN GOOD CONDITION - NON-INTERSTATE NHS



PERCENTAGE OF PAVEMENT IN HAMPTON ROADS IN POOR CONDITION - NON-INTERSTATE NHS



TRANSIT ASSET MANAGEMENT

MEASURES

- ▶ **Transit Asset Management (TAM) – Rolling Stock**
- ▶ **TAM – Equipment/Service Vehicles**
- ▶ **TAM - Infrastructure**
- ▶ **TAM - Facilities**

METHODOLOGY

This measure examines the condition of various aspects of the regional public transportation system. The Federal Transit Administration's (FTA) Performance-Based Planning final rule requires transit performance measures in the area of state of good repair, also referred to as transit asset management (TAM).

MPOs are required to establish regional targets and monitor progress for each of the assets using the performance measures in the following table:

| Asset Type | Performance Measure | Asset Classes |
|-----------------------------------|---|---|
| Rolling Stock | % of revenue vehicles within each asset class that have met or exceeded their useful life benchmark (ULB) | Buses, cutaway buses, ferry boats, light rail vehicles, trolley buses, vans |
| Equipment/Service Vehicles | % of vehicles that have met or exceeded their useful life benchmark (ULB) | Non-revenue automobiles, trucks and other rubber tire vehicles |
| Infrastructure | % of track segments, signals, and systems with performance restrictions | Light rail infrastructure |
| Facilities | % of facilities in each asset class rated under 3.0 on FTA's TERM scale | Passenger facilities, parking facilities, maintenance facilities, administrative facilities |

Three transit agencies operate within the Hampton Roads Metropolitan Planning Area – Hampton Roads Transit (HRT), the Williamsburg Area Transit Authority (WATA), and Suffolk Transit. HRT, as a larger Tier I transit agency, must develop and carry out their own TAM plans. As Tier II transit agencies, WATA and Suffolk Transit are eligible to participate in group TAM plans. WATA and Suffolk Transit elected to use the statewide targets that were established by the Virginia Department of Rail and Public Transportation (DRPT) for Tier II agencies.

TRANSIT ASSET MANAGEMENT

CURRENT/HISTORICAL CONDITIONS

The following table shows the transit asset management conditions in Hampton Roads in Fiscal Years 2018 through 2021:

| Rolling Stock | | | | |
|---|--------------|--------------|--------------|--------------|
| % of revenue vehicles within each asset class that have met or exceeded their useful life benchmark | | | | |
| | 2018 | 2019 | 2020 | 2021 |
| Buses | 36.7% | 26.9% | 25.1% | 10.9% |
| Cutaway Buses | 0% | 7.7% | 5.5% | 8.3% |
| Ferry Boat | 50.0% | 33.3% | 33.3% | 33.3% |
| Light Rail Vehicles | 0% | 0% | 0% | 0% |
| Minibus | 28.6% | 0% | 0% | 0% |
| Trolley Buses | 4.8% | 0% | 0% | 0% |
| Vans | 40.0% | 0% | 0% | 0% |

| Equipment/Service Vehicles | | | | |
|---|--------------|--------------|--------------|--------------|
| % of vehicles that have met or exceeded their useful life benchmark | | | | |
| | 2018 | 2019 | 2020 | 2021 |
| Non-Revenue/Service Vehicles | 91.3% | 74.0% | 89.7% | 86.5% |
| Trucks & Other Rubber Tire Vehicles | 64.0% | 12.5% | 17.6% | 35.0% |

| Infrastructure | | | | |
|---|-------------|-------------|-------------|-------------|
| % of track segments, signals, and systems with performance restrictions | | | | |
| | 2018 | 2019 | 2020 | 2021 |
| Light Rail Infrastructure | 2.8% | 2.2% | 5.0% | 8.3% |

| Facilities | | | | |
|---|--------------|--------------|--------------|--------------|
| % of facilities in each asset class rated under 3.0 on FTA's TERM scale | | | | |
| | 2018 | 2019 | 2020 | 2021 |
| Passenger/Parking | 9.1% | 9.1% | 0% | 0% |
| Maintenance | 14.3% | 14.3% | 14.3% | 14.3% |
| Administrative | 0% | 0% | 0% | 0% |

STATEWIDE 2023 TARGETS

The Virginia Department of Rail and Public Transportation established targets for Tier II transit agencies – such as WATA and Suffolk Transit – that elected to participate in the statewide group TAM plan. The FY 2023 targets are:

Rolling Stock

(% of revenue vehicles that have met or exceeded their useful life benchmark)

- **Buses** < 15%
- **Cutaway Buses** < 10%
- **Minibus** < 20%
- **Trolley Buses** < 15%
- **Vans** < 20%

Equipment/Service Vehicles

(% of vehicles that have met or exceeded their useful life benchmark)

- **Non-Revenue/Service Vehicles** < 30%
- **Trucks & Other Rubber Tire Vehs** < 30%

Facilities

(% of facilities in each asset class rated under 3.0 on FTA's TERM scale)

- **Passenger** < 15%
- **Maintenance** < 10%
- **Administrative** < 10%

There are no statewide targets for Tier I transit agencies such as HRT. Each Tier I transit agency must establish their own transit asset management targets.


TRANSIT ASSET MANAGEMENT

HRTPO 2023 TARGETS

The HRTPO established one-year (2023) regional transit asset management targets for each of the categories as shown to the right. **These regional targets are based on a weighted average of HRT, WATA, and Suffolk Transit Fiscal Year 2023 targets.**

ROLLING STOCK TARGETS

PERCENTAGE OF REVENUE VEHICLES THAT HAVE MET OR EXCEEDED THEIR USEFUL LIFE BENCHMARK



Rolling Stock

% of revenue vehicles that have met or exceeded their useful life benchmark

- ▶ **Buses** < 28%
- ▶ **Cutaway Buses** < 17%
- ▶ **Ferry Boat** < 20%
- ▶ **Light Rail Vehicles** 0%
- ▶ **Minibus** < 20%
- ▶ **Trolley Buses** 0%
- ▶ **Vans** 0%

Equipment/Service Vehicles

% of vehicles that have met or exceeded their useful life benchmark

- ▶ **Non-Revenue/Service Vehicles** < 26%
- ▶ **Trucks & Other Rubber Tire Vehicles** < 38%

Infrastructure

% of track segments, signals, and systems with performance restrictions

- ▶ **Light Rail Infrastructure** 0%

Facilities


% of facilities in each asset class rated under 3.0 on FTA's TERM scale

- ▶ **Passenger/Parking** < 1%
- ▶ **Maintenance** < 10%
- ▶ **Administrative** < 10%

TRANSIT ASSET MANAGEMENT


EQUIPMENT/SERVICE VEHICLES TARGETS

PERCENTAGE OF VEHICLES THAT HAVE MET OR EXCEEDED THEIR USEFUL LIFE BENCHMARK




FACILITIES TARGETS

PERCENTAGE OF FACILITIES IN EACH ASSET CLASS RATED UNDER 3.0 ON FTA'S TERM SCALE



INFRASTRUCTURE TARGETS

PERCENTAGE OF TRACK SEGMENTS, SIGNALS, AND SYSTEMS WITH PERFORMANCE RESTRICTIONS



TRANSIT ASSET MANAGEMENT

PROGRESS TOWARDS ACHIEVING TARGETS

HRTPO has established one-year transit asset management targets each year between 2019 and 2023. Each of these one-year regional targets is shown below. Information on whether Hampton Roads achieved its 2021 transit asset management targets based on the 2021 data is also detailed for each of the measures below:

► Rolling Stock - Buses

Targets – 41% ('19), 19% ('20), 10% ('21), 10% ('22), 28% ('23)

MISSING TARGET

A total of 10.9% of the bus fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is above the HRTPO's established target of 10%.

► Rolling Stock – Cutaway Buses

Targets – 10% ('19), 1% ('20), 1% ('21), 5% ('22), 17% ('23)

MISSING TARGET

A total of 8.3% of the cutaway bus fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is above the HRTPO's established target of 1%.

► Rolling Stock – Ferry Boat

Targets – 50% ('19), 33% ('20), 33% ('21), 25% ('22), 20% ('23)

SURPASSING TARGET

A total of 33% of the ferry boat fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which matches the HRTPO's established target of 33%.

► Rolling Stock – Light Rail Vehicles

Targets – 0% ('19), 0% ('20), 0% ('21), 0% ('22), 0% ('23)

SURPASSING TARGET

None of the light rail vehicle fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which matches the HRTPO's established target of 0%.

► Rolling Stock – Minibus

Targets – 20% ('19), 20% ('20), 20% ('21), 20% ('22), 20% ('23)

SURPASSING TARGET

None of the minibus fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is surpassing (below) the HRTPO's established target of 20%.

► Rolling Stock – Trolley Buses

Targets – 3.3% ('19), 3% ('20), 10% ('21), 1% ('22), 0% ('23)

SURPASSING TARGET

None of the trolley bus fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is surpassing (below) the HRTPO's established target of 10%.

► Rolling Stock – Vans

Targets – 25% ('19), 25% ('20), 25% ('21), 25% ('22), 0% ('23)

SURPASSING TARGET

None of the van fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is surpassing (below) the HRTPO's established target of 25%.

TRANSIT ASSET MANAGEMENT

► Equipment/Service Vehicles – Non-Revenue/Service Vehicles

Targets – 92% ('19), 66% ('20), 62% ('21), 62 ('22), 26% ('23)

MISSING TARGET

A total of 86.5% of the non-revenue/service vehicle fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is above the HRTPO's established target of 62%.

► Equipment/Service Vehicles – Trucks & Other Rubber Tire Vehicles

Targets – 70% ('19), 13% ('20), 17% ('21), 17% ('22), 38% ('23)

MISSING TARGET

A total of 35.0% of the trucks & other rubber tire vehicles service fleet in Hampton Roads met or exceeded the useful life benchmark in 2021, which is above the HRTPO's established target of 17%.

► Infrastructure – Light Rail Infrastructure

Targets – 2.6% ('19), 1.0% ('20), 4.0% ('21), 0.3% ('22), 0% ('23)

MISSING TARGET

A total of 8.3% of the light rail infrastructure in Hampton Roads had performance restrictions in 2021, which is above the HRTPO's established target of 4.0%.

► Facilities – Passenger/Parking

Targets – 0.9% ('19), 1.0% ('20), 1.0% ('21), 1.0% ('22), 1.0% ('23)

SURPASSING TARGET

None of the passenger and parking facilities in Hampton Roads rated under 3.0 on FTA's TERM Scale in 2021, which is surpassing (below) the HRTPO's established target of 1.0%.

► Facilities – Maintenance

Targets – 10% ('19), 10% ('20), 10% ('21), 10% ('22), 10% ('23)

MISSING TARGET

A total of 14.3% of the maintenance facilities in Hampton Roads rated under 3.0 on FTA's TERM Scale in 2021, which is above the HRTPO's established target of 10%.

► Facilities – Administrative

Targets – 10% ('19), 10% ('20), 10% ('21), 10% ('22), 10% ('23)

SURPASSING TARGET

None of the administrative facilities in Hampton Roads rated under 3.0 on FTA's TERM Scale in 2021, which is surpassing (below) the HRTPO's established target of 10%.

The three Hampton Roads transit agencies will continue to invest in capital assets using increased state and federal sources as well as new regional sources such as the Hampton Roads Regional Transit Fund (HRRTF).

TRANSIT SAFETY

MEASURES

- ▶ **Transit Fatalities**
- ▶ **Transit Injuries**
- ▶ **Transit Safety Events**
- ▶ **Transit System Reliability**

METHODOLOGY

Starting in 2021, the Federal Transit Administration (FTA) requires MPOs to establish regional transit safety targets and incorporate them into Transportation Improvement Programs (TIPs) and Long-Range Transportation Plans (LRTPs). MPOs are required to establish targets and monitor progress in the following transit safety areas for each mode (bus, demand response, light rail, and vanpool):

| Category | Measure |
|--------------------|--|
| Fatalities | Total number of reportable fatalities per year |
| | Rate per total vehicle revenue miles |
| Injuries | Total number of reportable injuries per year |
| | Rate per total vehicle revenue miles |
| Safety Events | Total number of safety events per year |
| | Rate per total vehicle revenue miles |
| System Reliability | Distance between major failures |

Safety events are defined as events that include the following if they occur on a transit right-of-way, transit infrastructure, at a transit revenue facility, at a transit facility during maintenance activity, or involving a transit revenue vehicle:

- A fatality confirmed within 30 days of the event
- An injury requiring immediate medical attention away from the scene for at least one person
- Property damage of \$25,000 or more
- Collisions involving transit revenue vehicles that require towing a transit vehicle or other non-transit vehicle away from the scene
- An evacuation for life safety reasons

For system reliability, major failures are defined as those that limit actual vehicle movement or impact safety, such as issues related to doors, brakes, engines, steering, axles, and vehicle suspension systems.

Similar to transit asset management, Hampton Roads Transit (HRT), as a Tier I transit agency, must develop their own Public Transportation Agency Safety Plan (PTASP). As Tier II transit agencies, the Williamsburg Area Transit Authority (WATA) and Suffolk Transit are using the statewide transit safety targets that were established in the [statewide PTASP](#) developed by the Virginia Department of Rail and Public Transportation.

TRANSIT SAFETY

CURRENT/HISTORICAL CONDITIONS

The following table shows the transit safety conditions in Hampton Roads for the years 2019, 2020 and 2021:

| Transit Fatalities | | | |
|--|------------|-------------|-------------|
| Total Number of Reportable Fatalities Per Year | | | |
| | 2019 | 2020 | 2021 |
| Buses | 0 | 1 | 1 |
| Demand Response | 0 | 0 | 0 |
| Light Rail | 0 | 0 | 0 |
| Vanpool | 0 | 0 | 0 |
| Rate per 100,000 Total Vehicle Revenue Miles | | | |
| | 2019 | 2020 | 2021 |
| Buses | 0.0 | 0.09 | 0.09 |
| Demand Response | 0.0 | 0.0 | 0.0 |
| Light Rail | 0.0 | 0.0 | 0.0 |
| Vanpool | 0.0 | 0.0 | 0.0 |

| Safety Events | | | |
|--|--------------|--------------|--------------|
| Total Number of Safety Events Per Year | | | |
| | 2019 | 2020 | 2021 |
| Buses | 66 | 65 | 39 |
| Demand Response | 1 | 4 | 6 |
| Light Rail | 8 | 7 | 4 |
| Vanpool | 0 | 0 | 0 |
| Rate per 100,000 Total Vehicle Revenue Miles | | | |
| | 2019 | 2020 | 2021 |
| Buses | 5.48 | 5.85 | 3.41 |
| Demand Response | 0.31 | 1.21 | 1.83 |
| Light Rail | 20.75 | 20.37 | 10.55 |
| Vanpool | 0 | 0 | 0 |

| Transit Injuries | | | |
|--|-------------|-------------|-------------|
| Total Number of Reportable Injuries Per Year | | | |
| | 2019 | 2020 | 2021 |
| Buses | 102 | 57 | 36 |
| Demand Response | 1 | 5 | 8 |
| Light Rail | 2 | 2 | 2 |
| Vanpool | 0 | 0 | 0 |
| Rate per 100,000 Total Vehicle Revenue Miles | | | |
| | 2019 | 2020 | 2021 |
| Buses | 8.47 | 5.13 | 3.14 |
| Demand Response | 0.31 | 1.51 | 2.44 |
| Light Rail | 5.19 | 5.82 | 5.27 |
| Vanpool | 0 | 0 | 0 |

| System Reliability | | | |
|---------------------------------|----------------|----------------|------------------|
| Distance Between Major Failures | | | |
| | 2019 | 2020 | 2021 |
| Buses | 12,509 | 17,060 | 19,637 |
| Demand Response | 135,748 | 368,039 | 1,638,518 |
| Light Rail | 9,402 | 13,745 | 11,492 |
| Vanpool | 693,712 | - | - |

TRANSIT SAFETY

STATEWIDE 2023 TARGETS

The Virginia Department of Rail and Public Transportation established targets for Tier II transit agencies – such as WATA and Suffolk Transit – that elected to participate in the statewide group PTASP. The statewide FY 2023 transit safety targets are:

Fatality Rate – 0 fatalities per 100,000 vehicle revenue miles
(Fatality rate for each mode)

Injury Rate – < 0.5 injuries per 100,000 vehicle revenue miles
(Injury rate for each mode)

Safety Event Rate – < 1 reportable event per 100,000 vehicle revenue miles
(Safety event rate for each mode)

Distance Between Major Failures – > 10,000 miles
(Distance for each mode)

There are no statewide targets for Tier I transit agencies such as HRT. Each Tier I transit agency must establish their own transit safety targets.

HRTPO 2023 TARGETS

The HRTPO established one-year (2023) regional transit safety targets for each of the categories as shown to the right. **These regional targets are based on a weighted average of HRT, WATA, and Suffolk Transit Fiscal Year 2023 targets.**

Transit Fatalities

Total Number of Reportable Fatalities/Rate per 100,000 Vehicle Revenue Miles

- ▶ **Buses** 0 / 0.0
- ▶ **Demand Response** 0 / 0.0
- ▶ **Light Rail** 0 / 0.0
- ▶ **Vanpool** 0 / 0.0

Transit Injuries

Total Number of Reportable Injuries/Rate per 100,000 Vehicle Revenue Miles

- ▶ **Buses** < 83 / < 7.62
- ▶ **Demand Response** 0 / 0.0
- ▶ **Light Rail** 0 / 0.0
- ▶ **Vanpool** 0 / 0.0

Transit Safety Events

Total Number of Reportable Events/Rate per 100,000 Vehicle Revenue Miles

- ▶ **Buses** < 71 / < 5.70
- ▶ **Demand Response** < 1 / < 0.04
- ▶ **Light Rail** < 5 / < 15.40
- ▶ **Vanpool** 0 / 0.0

Transit System Reliability


Average Distance between Major Failures in Miles

- ▶ **Buses** > 10,000
- ▶ **Demand Response** > 29,249
- ▶ **Light Rail** > 9,470
- ▶ **Vanpool** > 498,800

TRANSIT SAFETY


TRANSIT FATALITY TARGETS

TOTAL NUMBER OF REPORTABLE FATALITIES




TRANSIT INJURY TARGETS

TOTAL NUMBER OF REPORTABLE INJURIES




TRANSIT FATALITY RATE TARGETS

RATE PER 100,000 VEHICLE REVENUE MILES



TRANSIT INJURY RATE TARGETS


RATE PER 100,000 VEHICLE REVENUE MILES



TRANSIT SAFETY


TRANSIT SAFETY EVENT TARGETS

TOTAL NUMBER OF REPORTABLE SAFETY EVENTS




TRANSIT SYSTEM RELIABILITY TARGETS

DISTANCE BETWEEN MAJOR FAILURES IN MILES



TRANSIT SAFETY EVENT RATE TARGETS

RATE PER 100,000 VEHICLE REVENUE MILES



TRANSIT SAFETY

PROGRESS TOWARDS ACHIEVING TARGETS

Similar to transit asset management, data for measuring progress towards achieving transit safety targets is obtained from the National Transit Database (NTD). Information on whether Hampton Roads achieved its 2021 transit safety targets based on the 2021 data is also detailed for each of the measures below:

► Transit Fatalities

Targets – 0 for all modes and all years

Bus –

MISSING TARGET

All other Modes –

SURPASSING TARGET

A fatality occurred involving a bus in Hampton Roads in 2021, which is above the HRTPO's established target of 0 fatalities. No other modes experienced a fatality in 2021.

► Transit Fatality Rates

Targets – 0 per 100,000 vehicle revenue miles for all modes and years

Bus –

MISSING TARGET

All other Modes –

SURPASSING TARGET

A fatality occurred involving a bus in Hampton Roads in 2021, which is above the HRTPO's established target of 0 fatalities per 100,000 vehicle revenue miles. No other modes experienced a fatality in 2021.

► Transit Injuries

Targets – < 83 for bus for all years, 0 for all other modes

Bus, Vanpool –

SURPASSING TARGET

Demand Response, Light Rail –

MISSING TARGET

The number of transit injuries on bus (36) and vanpool (0) met or exceeded the targets for the year 2021. The number of injuries on demand response (8) and light rail (2), however, missed the target of zero for 2021.

► Transit Injury Rates

Targets – < 7.62 for bus for all years, 0 for all other modes

Bus, Vanpool –

SURPASSING TARGET

Demand Response, Light Rail –

MISSING TARGET

The rate of transit injuries on bus (3.14 injuries per 100,000 vehicle revenue miles) and vanpool (0) met or exceeded the targets for the year 2021. The rate of injuries on demand response (2.44) and light rail (5.27), however, missed the target of zero for 2021.

TRANSIT SAFETY

► Transit Safety Events

Targets – < 71 for bus, < 1 for demand response, < 5 for light rail, and 0 for vanpool for all years

Bus, Light Rail, Vanpool –

SURPASSING TARGET

Demand Response –

MISSING TARGET

The number of transit safety events on bus (39), light rail (4) and vanpool (0) all met or exceeded the targets for the year 2021. The number of events on demand response (6), however, missed the target of less than 1 for 2021.

► Transit System Reliability

Targets – > 10,000 miles for bus, > 29,249 miles for demand response, > 9,470 miles for light rail, > 498,800 for vanpool for all years

All Modes –

SURPASSING TARGET

The distance between major failures on bus (19,637 miles), demand response (1,638,518 miles), light rail (11,492 miles) and vanpool (no major failures) all surpassed the targets for the year 2021.

► Transit Safety Event Rates

Targets – < 5.70 for bus, < 0.04 for demand response, < 15.40 for light rail, and 0 for vanpool for all years

Bus, Light Rail, Vanpool –

SURPASSING TARGET

Demand Response –

MISSING TARGET

The rate of transit safety events on bus (3.41), light rail (10.55) and vanpool (0) all met or exceeded the targets for the year 2021. The rate of events on demand response (1.83), however, missed the target of less than 0.04 for 2021.


ROADWAY PERFORMANCE

MEASURES


- ▶ Interstate Travel Time Reliability (% reliable person-miles of travel)
- ▶ Non-Interstate National Highway System Travel Time Reliability (% reliable person-miles of travel)

METHODOLOGY

This measure examines the roadway performance of the National Highway System (NHS) based on the person-miles travelled that are classified as reliable. The reliability of the system is calculated using a metric referred to as the Level of Travel Time Reliability (LOTTR). The LOTTR is defined as the ratio of the 80th percentile travel time to the mean (50th percentile) travel time. Travel time information – which is provided through the National Performance Management Research Data Set (NPMRDS) – is collected throughout the year on each segment of the NHS in 15-minute intervals. An example of this calculation is shown below:





Travel times throughout the year are divided into four reporting periods: Weekday morning peak, weekday midday, weekday afternoon peak, and weekends. The time of day that each period represents is shown below:



A LOTTR ratio is calculated for each Interstate and Non-Interstate NHS segment by direction for each of these time periods over the course of an entire year. This produces a total of four LOTTR ratios for each Interstate and Non-Interstate NHS segment. Segments are considered to be not reliable if any of these four LOTTR ratios are 1.50 or greater. For a segment to be classified as reliable, all four LOTTR ratios must be below 1.50. An example of this calculation is shown on the next page:

ROADWAY PERFORMANCE



This procedure is followed for each Interstate and Non-Interstate NHS segment to determine whether the segment is reliable or not reliable. Each of the reliable individual Interstate and Non-Interstate NHS segments are then multiplied by the length of that particular segment, the annual vehicle volume on that segment, and an occupancy factor based on the average number of persons per vehicle that converts vehicular travel to person travel. These products are added together for the entire Interstate and Non-Interstate NHS network and divided by the same factors for the entire system to produce the regional percentage of reliable person-miles of travel on the Interstate and Non-Interstate NHS systems. An example of this calculation is shown to the right:


ROADWAY PERFORMANCE

CURRENT/HISTORICAL CONDITIONS

The following charts show the percentage of reliable person-miles of travel in Hampton Roads and throughout Virginia for 2016 through 2021. The chart on the left reflects the data for the Interstate system, and the chart on the right reflects the Non-Interstate NHS.

In addition, the maps on the following page show the LOTTR for Interstate and non-Interstate NHS in Hampton Roads in 2021.

PERCENTAGE OF RELIABLE PERSON-MILES OF TRAVEL - INTERSTATE (2016 - 2021)




STATEWIDE 4-YEAR TARGETS (2021-2025)

- ▶ Percentage of Reliable Person-Miles of Travel - Interstate > 85%
- ▶ Percentage of Reliable Person-Miles of Travel - Non-Interstate NHS > 88%


The statewide four-year targets established by the Commonwealth Transportation Board (CTB) are based on projections using a model created for VDOT that estimates future reliability values for both the state and each MPO based on 30 traffic and roadway characteristic variables.

PERCENTAGE OF RELIABLE PERSON-MILES OF TRAVEL – NON-INTERSTATE NHS (2016 - 2021)




ROADWAY PERFORMANCE

LEVEL OF TRAVEL TIME RELIABILITY
INTERSTATE (2021)



Source: RITIS using NPMRDS data

LEVEL OF TRAVEL TIME RELIABILITY
NON-INTERSTATE NHS (2021)



Source: RITIS using NPMRDS data


ROADWAY PERFORMANCE

HRTPO 4-YEAR TARGETS (2022-2025)

The HRTPO established four-year targets of greater than 94% of the Interstate travel in the region being reliable, and greater than 88% of the Non-Interstate NHS travel being reliable. **Both of these percentages match the VDOT travel time reliability model projections for Hampton Roads.**

- ▶ Interstate Travel Time Reliability (% reliable person-miles) **> 94%**
- ▶ Non-Interstate NHS Travel Time Reliability (% reliable person-miles) **> 88%**

PERCENTAGE OF RELIABLE PERSON-MILES OF TRAVEL – INTERSTATE



ROADWAY PERFORMANCE

PROGRESS TOWARDS ACHIEVING TARGETS

Hampton Roads exceeded the 2021 targets in both roadway performance measures. More details on each of the two roadway performance measures is shown below:

► Percentage of Reliable Person-Miles of Travel - Interstate System

SURPASSING TARGET


At 90%, this is surpassing (above) the 82.0% level that was established as the original 2021 target. For 2025, the new regional target has been set at 94%.

► Percentage of Reliable Person-Miles of Travel – Non-Interstate NHS

SURPASSING TARGET

At 94%, this is surpassing (above) the 82.5% level that was established as the original 2021 target. For 2025, the new regional target has been set at 88%.

PERCENTAGE OF RELIABLE PERSON-MILES OF TRAVEL - NON-INTERSTATE NHS




MEASURES


- **Truck Travel Time Reliability (TTTR) Index on the Interstate system**

METHODOLOGY

This measure examines the reliability of moving freight via truck on the regional Interstate system. The reliability of freight movement is calculated using a metric referred to as the Truck Travel Time Reliability (TTTR) Index. The TTTR ratio is defined as the ratio of the 95th percentile travel time for trucks to the mean (50th percentile) travel time for trucks. This travel time information – which is provided through the National Performance Management Research Data Set (NPMRDS) – is collected throughout the year on each segment of the Interstate system in 15-minute intervals. An example of calculating this ratio is shown below:




Truck travel times throughout the year are divided into five reporting periods: Weekday morning peak, weekday midday, weekday afternoon peak, weekends, and overnight. The time of day that each period represents is shown below:



A TTTR ratio is calculated for each Interstate segment by direction for each of these time periods over the course of an entire year. This produces a total of five TTTR ratios for each Interstate segment. For each segment, the maximum of these five TTTR ratios is determined and used to calculate the regional index. This calculation is highlighted on the next page:

FREIGHT

| | | |
|---|------------|--|
| $\frac{\text{Longer Truck Travel Time (95th)}}{\text{Normal Truck Travel Time (50th)}} = \frac{\text{\# seconds}}{\text{\# seconds}} = \text{Truck Travel Time Reliability (TTTR) Ratio}$ | | |
| Truck Travel Time Reliability (TTTR) (Single Segment, Interstate Highway System) | | |
| Monday – Friday | 6am – 10am | $\text{TTTR} = \frac{72 \text{ sec}}{50 \text{ sec}} = 1.44$ |
| | 10am – 4pm | $\text{TTTR} = 1.39$ |
| | 4pm – 8pm | $\text{TTTR} = 1.49$ |
| Weekends | 6am – 8pm | $\text{TTTR} = 1.31$ |
| Overnight | 8pm – 6am | $\text{TTTR} = 1.20$ |
| Maximum TTTR 1.49 | | |




These individual Interstate segment Maximum TTTR ratios are then multiplied by the length of that particular segment. These products are added together for the entire region and divided by the total directional length of the regional Interstate system to produce the regional Truck Travel Time Reliability Index. An example of this calculation is shown to the right:

CURRENT/HISTORICAL CONDITIONS

The following chart shows the Truck Travel Time Reliability (TTTR) Index for the Interstate system in Hampton Roads and throughout Virginia for 2016 through 2021.

In addition, the map to the right graphically shows the TTTR on Interstate roadways in Hampton Roads in 2021.

TRUCK TRAVEL TIME RELIABILITY INDEX - INTERSTATE (2016 – 2021)




STATEWIDE 4-YEAR TARGETS (2021-2025)

- ▶ **Truck Travel Time Reliability (TTTR) Index - Interstate** < 1.64

The statewide four-year target established by the Commonwealth Transportation Board (CTB) is based on projections using a model created for VDOT that estimates future reliability values for both the state and each MPO based on 30 traffic and roadway characteristic variables.

TRUCK TRAVEL TIME RELIABILITY INDEX - INTERSTATE (2021)



Source: RITIS using NPMRDS data.


FREIGHT

HRTPO 4-YEAR TARGETS (2021-2025)

The HRTPO established a four-year target for the Truck Travel Time Reliability Index on the Interstate system of less than 1.99. This percentage matches VDOT's truck travel time reliability model projections for Hampton Roads.

- ▶ **Truck Travel Time Reliability Index (Interstate System) < 1.99**

TRUCK TRAVEL TIME RELIABILITY INDEX – INTERSTATE



PROGRESS TOWARDS ACHIEVING TARGETS

Hampton Roads surpassed the 2021 target in the freight measure as shown below:

- ▶ **Truck Travel Time Reliability Index (Interstate System)**

SURPASSING TARGET

At 1.81, this is surpassing (below) the 2.13 level that was established as the original 2021 target. For 2025, the new regional target has been set at 1.99.

SUMMARY

The Moving Ahead for Progress in the 21st Century (MAP-21) surface transportation legislation established a performance- and outcome-based program. As part of this program, States and Metropolitan Planning Organizations (MPOs) prepare and use a set of federally-established performance measures that are tied to national performance goals.

Each MPO must set regional targets in the areas of roadway safety, pavement condition, bridge condition, transit asset management, transit safety, roadway performance, and freight. These performance measures and targets must be reported based on the MPO's Metropolitan Planning Area (MPA). The Hampton Roads MPA is comprised of 15 localities including all of Chesapeake, Hampton, Isle of Wight County, James City County, Newport News, Norfolk, Poquoson, Portsmouth, Suffolk, Virginia Beach, Williamsburg, and York County and portions of Franklin, Gloucester County, and Southampton County.

For roadway safety, transit asset management, and transit safety, targets are established for a one-year time horizon and must be set on an annual basis. For the bridge condition, pavement condition, roadway performance and freight measures, MPO targets are established for a four-year time horizon, whereas states establish both two-year and four-year targets. For target setting, MPOs may adopt the statewide targets but report metrics specific to the MPA; select unique, MPO specific targets, and report metrics specific to the MPA; or use a combination of statewide and unique targets.

Setting the HRTPO targets – which are shown on the following pages – is a collaborative effort. The Transportation Technical Advisory Committee (TTAC) recommended targets for the HRTPO Board to consider. In order to assist the TTAC, the committee formed a Regional Performance Measures Working Group. This group includes staff from localities, transit agencies, VDOT, and subject-matter experts.

This Regional Performance Measures – System Performance Report is updated on an annual basis to reflect revised targets as well as progress towards meeting the established targets. The progress that Hampton Roads is making towards meeting the targets is summarized on the following pages.

In addition to this document, the HRTPO also maintains a Regional Performance Measures and Targets website that includes information on each of these performance measures as well as the basis for selecting each regional target. The HRTPO Regional Performance Measures and Targets website is <https://www.hrtpo.org/page/regional-performance-measures-and-targets>.

SUMMARY

CURRENT HAMPTON ROADS REGIONAL TARGETS ESTABLISHED BY THE HRTPO BOARD AND PROGRESS TOWARD ACHIEVING ESTABLISHED TARGETS

ONE-YEAR TARGETS ROADWAY SAFETY AND TRANSIT ASSET MANAGEMENT

| Area | Measures | HRTPO Approved One-Year Target (2023) | Progress Towards Meeting Target (as of Most Recent Data) |
|--------------------------|--|---------------------------------------|--|
| Roadway Safety | Fatalities | 136 | MISSING TARGET |
| | Fatality Rate | 0.917 | MISSING TARGET |
| | Serious Injuries | 1,513 | MISSING TARGET |
| | Serious Injury Rate | 10.21 | MISSING TARGET |
| | Non-Motorized Fatalities & Serious Injuries | 177 | MISSING TARGET |
| Transit Asset Management | <u>Rolling Stock</u> - % of revenue vehicles within each asset class that have met or exceeded their useful life benchmark | | |
| | Bus | < 28% | MISSING TARGET |
| | Cutaway Buses | < 17% | MISSING TARGET |
| | Ferry Boat | < 20% | SURPASSING TARGET |
| | Light Rail Vehicles | 0% | SURPASSING TARGET |
| | Minibus | < 20% | SURPASSING TARGET |
| | Trolley Buses | 0% | SURPASSING TARGET |
| | Van | 0% | SURPASSING TARGET |
| | <u>Equipment/Service Vehicles</u> - % of vehicles that have met or exceeded their useful life benchmark | | |
| | Non-Revenue/ Service Vehicles | < 26% | MISSING TARGET |
| Infrastructure | Trucks & Other Rubber Tire Vehs | < 38% | MISSING TARGET |
| | <u>Infrastructure</u> - % of track segments, signals, and systems with performance restrictions | | |
| | Light Rail Infrastructure | 0% | MISSING TARGET |
| | <u>Facilities</u> - % of facilities in each asset class rated under 3.0 on FTA's TERM scale | | |
| | Passenger/Parking | < 1% | SURPASSING TARGET |
| Maintenance | Maintenance | < 10% | MISSING TARGET |
| | Administrative | < 10% | SURPASSING TARGET |

SUMMARY

CURRENT HAMPTON ROADS REGIONAL TARGETS ESTABLISHED BY THE HRTPO BOARD AND PROGRESS TOWARD ACHIEVING ESTABLISHED TARGETS

ONE-YEAR TARGETS

TRANSIT SAFETY

| Area | Measures | HRTPO Approved One-Year Target (2023) | Progress Towards Meeting Target (as of Most Recent Data) |
|----------------|------------------------------|---------------------------------------|--|
| Transit Safety | <u>Transit Fatalities</u> | | |
| | Bus | 0 | MISSING TARGET |
| | Demand Response | 0 | SURPASSING TARGET |
| | Light Rail | 0 | SURPASSING TARGET |
| | Vanpool | 0 | SURPASSING TARGET |
| | <u>Transit Fatality Rate</u> | | |
| | Bus | 0.0 | MISSING TARGET |
| | Demand Response | 0.0 | SURPASSING TARGET |
| | Light Rail | 0.0 | SURPASSING TARGET |
| | Vanpool | 0.0 | SURPASSING TARGET |
| | <u>Transit Injuries</u> | | |
| | Bus | < 83 | SURPASSING TARGET |
| | Demand Response | 0 | MISSING TARGET |
| | Light Rail | 0 | MISSING TARGET |
| | Vanpool | 0 | SURPASSING TARGET |
| | <u>Transit Injury Rate</u> | | |
| | Bus | < 7.62 | SURPASSING TARGET |
| | Demand Response | 0.0 | MISSING TARGET |
| | Light Rail | 0.0 | MISSING TARGET |
| | Vanpool | 0.0 | SURPASSING TARGET |
| | <u>Safety Events</u> | | |
| | Bus | < 71 | SURPASSING TARGET |
| | Demand Response | < 1 | MISSING TARGET |
| | Light Rail | < 5 | SURPASSING TARGET |
| | Vanpool | 0 | SURPASSING TARGET |
| | <u>Safety Event Rate</u> | | |
| | Bus | < 5.70 | SURPASSING TARGET |
| | Demand Response | < 0.04 | MISSING TARGET |
| | Light Rail | < 15.40 | SURPASSING TARGET |
| | Vanpool | 0.0 | SURPASSING TARGET |
| | <u>System Reliability</u> | | |
| | Bus | > 10,000 | SURPASSING TARGET |
| | Demand Response | > 29,249 | SURPASSING TARGET |
| | Light Rail | > 9,470 | SURPASSING TARGET |
| | Vanpool | > 498,800 | SURPASSING TARGET |

SUMMARY

CURRENT HAMPTON ROADS REGIONAL TARGETS ESTABLISHED BY THE HRTPO BOARD AND PROGRESS TOWARD ACHIEVING ESTABLISHED TARGETS

FOUR-YEAR TARGETS BRIDGE CONDITION, PAVEMENT CONDITION, ROADWAY PERFORMANCE, AND FREIGHT

| Area | Measures | HRTPO Approved Four-Year Target (2025) | Progress Towards Meeting Target (as of Most Recent Data) |
|---------------------|--|--|--|
| Bridge Condition | NHS bridge deck area in good condition | > 25.1% | MISSING TARGET |
| | NHS bridge deck area in poor condition | < 3.6% | MISSING TARGET |
| Pavement Condition | Interstate System pavement in good condition | > 45% | SURPASSING TARGET |
| | Interstate System pavement in poor condition | < 3% | SURPASSING TARGET |
| | Non-Interstate System NHS pavement in good condition | > 14% | MISSING TARGET |
| | Non-Interstate System NHS pavement in poor condition | < 5% | SURPASSING TARGET |
| Roadway Performance | Interstate Travel Time Reliability | > 94% | SURPASSING TARGET |
| | Non-Interstate NHS Travel Time Reliability | > 88% | SURPASSING TARGET |
| Freight | Truck Travel Time Reliability Index | < 1.99 | SURPASSING TARGET |

STATE PERFORMANCE MEASURES

In 2009, the General Assembly of Virginia passed legislation codifying regional transportation performance measurement. In response to the legislation, HRTPO staff, in cooperation with other Virginia metropolitan areas and Virginia's Office of Intermodal Planning and Investment (OIPPI), developed a list of regional performance measures (RPMs). The HRTPO Board approved this list in January 2011 and the Commonwealth Transportation Board (CTB) approved it in June 2011.

The Hampton Roads regional performance measures (RPMs) include approximately 70 measures, which are organized in the following 12 categories:

- ▶ Transportation System Measures
 - ▶ Congestion Reduction
 - ▶ Safety
 - ▶ Transit Usage
 - ▶ HOV Usage
 - ▶ Job-to-Housing Ratios
 - ▶ Job and Housing Access to Transit
 - ▶ Job and Housing Access to Pedestrian Facilities
 - ▶ Air Quality
 - ▶ Movement of Freight
 - ▶ Vehicle-Miles Traveled (VMT)
 - ▶ Maintenance
- ▶ Financial System Measures

The first ten categories were suggested by the Commonwealth; the last two – Maintenance and Financial – were added by the Transportation Technical Advisory Committee (TTAC).

In April 2012, the HRTPO Board approved a set of targets for its RPMs. Lacking a basis for setting numerical targets, the HRTPO, with the approval of the TTAC's RPM Task Force, decided to set trend targets – increasing a particular value, decreasing a particular value, or maintaining that particular value.

This HRTPO Regional Performance Measures effort is updated annually as part of this System Performance Report. The RPM values and targets are presented on the following pages. The desired direction of each target and the progress in meeting these goals is indicated by the following:

-  goal: maintain value
-  goal: increase value
-  goal: decrease value

- Green indicates that the actual trend is following the desired trend
- Orange indicates that the actual trend is directionally opposite to the desired trend
- Blue indicates an unclear trend.

STATE PERFORMANCE MEASURES

| | Data Source | | | | | | | | | | | | | Desired | |
|---|-----------------------|-------------|-------------|-------------|-------------|------------|------------|------------|------------|------------|------------|------------|------------|-----------|---|
| | | Year 2010 | Year 2011 | Year 2012 | Year 2013 | Year 2014 | Year 2015 | Year 2016 | Year 2017 | Year 2018 | Year 2019 | Year 2020 | Year 2021 | Year 2022 | Trend |
| A. Transportation System Performance Measures¹³ | | | | | | | | | | | | | | | |
| 1. congestion reduction | | | | | | | | | | | | | | | |
| Annual Delay, hours per peak auto commuter | TTI | 38 | 39 | 39 | 41 | 43 | 44 | 46 | 46 | 44 | 43 | 22 | n.a. | n.a. |  |
| Annual Excess Fuel Consumed, gallons per peak auto commuter | TTI | 16 | 16 | 16 | 16 | 16 | 15 | 15 | 15 | 15 | 15 | 8 | n.a. | n.a. |  |
| Travel Time Index (extra time during peak period), % | TTI/FHWA | 1.17 | 1.17 | 1.18 | 1.18 | 1.17 | 1.17 | 1.17 | 1.17 | 1.16 | 1.16 | 1.06 | 1.17 | n.a. |  |
| 2. safety | | | | | | | | | | | | | | | |
| Annual Roadway Fatalities, number | DMV ²⁴ | 121 | 136 | 99 | 131 | 125 | 121 | 125 | 155 | 139 | 147 | 150 | 179 | n.a. |  |
| Annual Roadway Fatalities, per 100 million VMT ²⁵ | DMV ²⁴ | 0.89 | 0.86 | 0.81 | 0.84 | 0.88 | 0.84 | 0.84 | 1.03 | 0.93 | 0.96 | 1.11 | 1.28 | n.a. |  |
| Annual Roadway Injuries, number | DMV ²⁴ | 13,449 | 14,038 | 15,034 | 15,432 | 14,715 | 14,955 | 16,628 | 16,578 | 16,448 | 16,895 | 15,002 | 16,531 | n.a. |  |
| Annual Roadway Injuries, per million VMT | DMV ²⁴ | 0.90 | 0.96 | 1.04 | 1.07 | 1.04 | 1.03 | 1.11 | 1.11 | 1.10 | 1.11 | 1.11 | 1.18 | n.a. |  |
| Annual Roadway Crashes, number | DMV ²⁴ | 23,142 | 24,115 | 25,192 | 25,374 | 24,874 | 25,310 | 26,853 | 26,765 | 26,916 | 26,250 | 23,466 | 26,170 | n.a. |  |
| Annual Roadway Crashes, per million VMT | DMV ²⁴ | 1.55 | 1.65 | 1.74 | 1.77 | 1.76 | 1.75 | 1.80 | 1.79 | 1.81 | 1.72 | 1.74 | 1.87 | n.a. |  |
| Annual Transit Fatalities, number | FTA ⁶ | 0 | 1 | 1 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 1 | 1 | n.a. |  |
| Annual Transit Fatalities, per 100 million PMT | FTA ⁶ | 0.00 | 0.85 | 0.81 | 0.00 | 0.00 | 0.00 | 3.65 | 0.00 | 0.00 | 0.00 | 1.80 | 2.81 | n.a. |  |
| Annual Transit Injuries, number | FTA ⁶ | 135 | 113 | 73 | 95 | 98 | 123 | 187 | 114 | 101 | 105 | 64 | 46 | n.a. |  |
| Annual Transit Injuries, per 100 million PMT | FTA ⁶ | 118 | 96 | 59 | 86 | 101 | 145 | 227 | 130 | 127 | 134 | 115 | 129 | n.a. |  |
| Annual Transit Collisions ¹⁹ , number | FTA ⁶ | 40 | 30 | 26 | 35 | 30 | 39 | 49 | 79 | 79 | 76 | 89 | 42 | n.a. |  |
| Annual Transit Collisions ¹⁹ , per 100 million PMT | FTA ⁶ | 35 | 26 | 21 | 32 | 31 | 46 | 60 | 90 | 99 | 97 | 160 | 118 | n.a. |  |
| Annual Aviation Fatalities ²² , number ²³ | NTSB | 1 | 2 | 0 | 8 | 0 | 3 | 0 | 0 | 3 | 0 | 0 | 0 | 1 |  |
| Annual Aviation Accidents ²² , number ²³ | NTSB | 8 | 3 | 1 | 5 | 3 | 3 | 9 | 4 | 4 | 4 | 3 | 0 | 4 |  |
| Annual Hwy-Rail Crossing Accidents ²⁰ , per million population | FRA | 2 | 1 | 4 | 4 | 5 | 3 | 3 | 3 | 5 | 5 | 5 | 5 | 3 |  |
| 3. transit usage | | | | | | | | | | | | | | | |
| Annual Unlinked Passenger Trips (UPT), number | APTA/FTA ⁶ | 18,646,984 | 19,371,225 | 21,234,400 | 21,361,191 | 19,987,547 | 19,085,376 | 17,942,371 | 16,814,136 | 15,753,209 | 15,083,291 | 8,041,122 | 7,183,188 | 7,606,041 |  |
| Annual Unlinked Passenger Trips (UPT), per capita ²¹ | HRTPO Calc. | 13 | 13 | 14 | 14 | 13 | 12 | 12 | 11 | 10 | 10 | 5 | 5 | 5 |  |
| Annual Vehicle Revenue Miles (VRM), number | FTA ⁶ | 15,972,878 | 16,016,548 | 16,158,133 | 15,634,645 | 15,552,017 | 16,084,113 | 16,857,027 | 16,963,577 | 16,719,945 | 16,985,301 | 15,586,906 | 15,453,212 | n.a. |  |
| Annual Vehicle Revenue Miles (VRM), per capita ²¹ | HRTPO Calc. | 11 | 11 | 11 | 10 | 10 | 10 | 11 | 11 | 11 | 11 | 10 | 10 | n.a. |  |
| Annual Passenger Miles Traveled (PMT), number | FTA ⁶ | 114,165,464 | 117,148,805 | 123,461,216 | 110,291,173 | 96,842,639 | 84,926,722 | 82,243,560 | 87,652,931 | 79,496,447 | 78,201,357 | 55,654,185 | 35,559,644 | n.a. |  |
| Annual Passenger Miles Traveled (PMT), per capita ²¹ | HRTPO Calc. | 77 | 78 | 82 | 72 | 63 | 55 | 53 | 57 | 52 | 51 | 36 | 23 | n.a. |  |
| Passengers Boarding or Departing Amtrak Trains (HR) ³² | Amtrak | 163,405 | 175,494 | 195,263 | 229,524 | 215,578 | 221,917 | 211,887 | 214,501 | 204,375 | 214,568 | 134,900 | 163,458 | 248,519 |  |
| Endpoint On-Time Performance, Amtrak (Rich/NN/Nor) ^{5 32} | Amtrak | n.a. | 76% | 85% | 84% | 73% | 71% | 78% | 73% | 69% | 75% | 83% | 80% | n.a. |  |
| Operating Cost Ratio ³⁰ , Amtrak ("Washington-NN" & "Washington-Norfolk") ⁵ | Amtrak | n.a. | 0.99 | 0.87 | 0.98 | 0.76 | 0.81 | 0.76 | 0.78 | 0.80 | 0.83 | 1.13 | 1.17 | 1.45 |  |

See page 51 for an explanation of footnotes.

STATE PERFORMANCE MEASURES

| | Data Source | Year 2010 | Year 2011 | Year 2012 | Year 2013 | Year 2014 | Year 2015 | Year 2016 | Year 2017 | Year 2018 | Year 2019 | Year 2020 | Year 2021 | Year 2022 | Desired Trend |
|--|---------------------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|---------------|
| 4. HOV usage | | | | | | | | | | | | | | | |
| Persons per Hour per HOV Ln During Peak Period, avg of count stations | VDOT | 685 | 571 | 638 | 598 | 612 | 525 | 679 | 717 | 722 | 901 | 542 | 930 | n.a. | Blue ↑ |
| # of Park and Ride Spaces | VDOT | n.a. | n.a. | 4,423 | n.a. | n.a. | 4,193 | 3,069 | 3,075 | 3,075 | 4,124 | n.a. | n.a. | 2,692 | Orange ↑ |
| # of Occupied Park and Ride Spaces, per 100,000 population | VDOT | n.a. | n.a. | n.a. | n.a. | n.a. | 64 | 63 | 56 | 62 | 57 | n.a. | n.a. | 24 | Orange ↑ |
| % of Commuters with Journey-to-Work via Carpool ¹⁰ | Census | 9.4% | 8.1% | 8.9% | 8.3% | 8.2% | 7.8% | 9.3% | 7.9% | 8.5% | 7.8% | n.a. | 7.8% | n.a. | Blue ↓ |
| 5. job-to-housing ratios | | | | | | | | | | | | | | | |
| Ratio of Jobs to Labor Force ² | | | | | | | | | | | | | | | Orange ↓ |
| Hampton Roads | VWC ³⁴ & HRPDC | 0.92 | 0.91 | 0.92 | 0.92 | 0.90 | 0.93 | 0.93 | 0.92 | 0.92 | 0.91 | 0.91 | 0.89 | n.a. | Orange ↓ |
| Chesapeake | VWC ³⁴ & HRPDC | 0.90 | 0.89 | 0.88 | 0.87 | 0.86 | 0.88 | 0.87 | 0.86 | 0.86 | 0.85 | 0.86 | 0.85 | n.a. | Orange ↓ |
| Franklin | VWC ³⁴ & HRPDC | 1.24 | 1.26 | 1.30 | 1.31 | 1.29 | 1.34 | 1.33 | 1.26 | 1.27 | 1.24 | 1.26 | 1.20 | n.a. | Orange ↓ |
| Gloucester | VWC ³⁴ & HRPDC | 0.51 | 0.51 | 0.52 | 0.52 | 0.50 | 0.51 | 0.51 | 0.50 | 0.50 | 0.49 | 0.51 | 0.50 | n.a. | Orange ↓ |
| Hampton | VWC ³⁴ & HRPDC | 0.92 | 0.90 | 0.91 | 0.90 | 0.88 | 0.89 | 0.90 | 0.89 | 0.88 | 0.86 | 0.84 | 0.82 | n.a. | Orange ↓ |
| Isle of Wight | VWC ³⁴ & HRPDC | 0.58 | 0.55 | 0.57 | 0.59 | 0.58 | 0.60 | 0.60 | 0.58 | 0.59 | 0.57 | 0.57 | 0.56 | n.a. | Orange ↓ |
| James City | VWC ³⁴ & HRPDC | 0.87 | 0.86 | 0.87 | 0.84 | 0.84 | 0.85 | 0.87 | 0.85 | 0.86 | 0.85 | 0.76 | 0.78 | n.a. | Orange ↓ |
| Newport News | VWC ³⁴ & HRPDC | 1.15 | 1.16 | 1.16 | 1.15 | 1.15 | 1.16 | 1.14 | 1.15 | 1.19 | 1.20 | 1.22 | 1.20 | n.a. | Orange ↓ |
| Norfolk | VWC ³⁴ & HRPDC | 1.33 | 1.33 | 1.32 | 1.30 | 1.28 | 1.34 | 1.34 | 1.33 | 1.33 | 1.30 | 1.31 | 1.28 | n.a. | Orange ↓ |
| Poquoson | VWC ³⁴ & HRPDC | 0.30 | 0.29 | 0.29 | 0.27 | 0.27 | 0.28 | 0.29 | 0.30 | 0.30 | 0.29 | 0.29 | 0.29 | n.a. | Orange ↓ |
| Portsmouth | VWC ³⁴ & HRPDC | 1.03 | 1.04 | 1.05 | 1.07 | 1.05 | 1.08 | 1.06 | 1.04 | 1.05 | 1.04 | 1.07 | 1.03 | n.a. | Orange ↓ |
| Southampton | VWC ³⁴ & HRPDC | 0.43 | 0.41 | 0.42 | 0.41 | 0.41 | 0.43 | 0.43 | 0.42 | 0.42 | 0.41 | 0.40 | 0.40 | n.a. | Orange ↓ |
| Suffolk | VWC ³⁴ & HRPDC | 0.65 | 0.64 | 0.69 | 0.68 | 0.68 | 0.71 | 0.73 | 0.73 | 0.75 | 0.75 | 0.76 | 0.77 | n.a. | Orange ↓ |
| Virginia Beach | VWC ³⁴ & HRPDC | 0.77 | 0.76 | 0.76 | 0.77 | 0.77 | 0.79 | 0.80 | 0.80 | 0.79 | 0.79 | 0.78 | 0.77 | n.a. | Orange ↓ |
| Williamsburg | VWC ³⁴ & HRPDC | 2.42 | 2.18 | 2.18 | 2.14 | 2.09 | 2.11 | 2.06 | 2.04 | 2.01 | 1.97 | 1.74 | 1.74 | n.a. | Orange ↓ |
| York | VWC ³⁴ & HRPDC | 0.71 | 0.71 | 0.70 | 0.70 | 0.69 | 0.71 | 0.71 | 0.69 | 0.68 | 0.67 | 0.63 | 0.63 | n.a. | Orange ↓ |
| Jobs - Labor Force ² Regional Linear Dissimilarity Index, 0.0 to 1.0 ³ | VWC ³⁴ & HRPDC | 0.11 | 0.11 | 0.11 | 0.11 | 0.10 | 0.11 | 0.10 | 0.10 | 0.11 | 0.11 | 0.11 | 0.11 | n.a. | Green ↑ |
| % of Workers Working Outside Locality (City/County) in Which They Live | Census | 48% | 47% | 49% | 46% | 47% | 49% | 48% | 48% | 47% | 48% | n.a. | 43% | n.a. | Blue ↓ |
| Mean Travel Time to Work, minutes | Census | 23.7 | 23.3 | 24.0 | 24.0 | 24.1 | 24.8 | 24.0 | 24.4 | 25.0 | 24.6 | n.a. | 24.2 | n.a. | Green ↑ |
| 6. job and housing access to transit | | | | | | | | | | | | | | | |
| % of Employment in TAZ ¹ Served by Transit ¹⁸ | HRTPO ¹ | n.a. | 84% | 84% | 84% | 84% | 85% | 85% | 84% | 84% | 84% | 84% | 84% | n.a. | Blue ↑ |
| % of Households in TAZ ¹ Served by Transit ¹⁸ | HRTPO ¹ | n.a. | 73% | 73% | 73% | 73% | 75% | 75% | 74% | 74% | 74% | 74% | 74% | n.a. | Blue ↓ |
| 7. job and housing access to pedestrian facilities | | | | | | | | | | | | | | | |
| % of Housing Units ⁹ in areas ¹⁷ with 1%+ Walk-To-Work Mode Share | CTPP & ACS ³³ | n.a. | 37% | 38% | n.a. | 38% | n.a. | Blue ↑ |
| 8. air quality | | | | | | | | | | | | | | | |
| Annual # of Days when Ozone Levels were Above 8-Hour Standard | DEQ | 6 | 7 | 3 | 0 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | n.a. | 0 |
| NOx ⁷ (from motor vehicles), tons per day (near future) ¹⁵ | VDOT | n.a. | 43 | n.a. | n.a. | n.a. | n.a. | n.a. | 31.4 | n.a. | n.a. | n.a. | n.a. | n.a. | 32 |
| NOx ⁷ (from motor vehicles), grams per capita per day (near future) ¹⁵ | VDOT | n.a. | 23 | n.a. | n.a. | n.a. | n.a. | n.a. | 16.5 | n.a. | n.a. | n.a. | n.a. | n.a. | Green ↓ |
| VOC ⁷ (from motor vehicles), tons per day (near future) ¹⁵ | VDOT | n.a. | 35 | n.a. | n.a. | n.a. | n.a. | n.a. | 20.9 | n.a. | n.a. | n.a. | n.a. | n.a. | 28 |
| VOC ⁷ (from motor vehicles), grams per capita per day (near future) ¹⁵ | VDOT | n.a. | 19 | n.a. | n.a. | n.a. | n.a. | n.a. | 10.9 | n.a. | n.a. | n.a. | n.a. | n.a. | Green ↓ |
| CO ₂ (greenhouse gas, from motor veh's), tons per day (near future) ¹⁵ | VDOT ¹⁶ | n.a. | 22,464 | n.a. | Blue ↓ |
| CO ₂ (greenhouse gas, from motor veh's), grams/capita/day (near future) ¹⁵ | VDOT ¹⁶ | n.a. | 12,076 | n.a. | Blue ↓ |

See page 51 for an explanation of footnotes.

STATE PERFORMANCE MEASURES

| | | | | | | | | | | | | | | | Desired |
|--|------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|---------|
| | | | | | | | | | | | | | | | Trend |
| 9. movement of freight | | | | | | | | | | | | | | | |
| Shares (%) of General Cargo Handled by Port of Virginia, by container | VPA | | | | | | | | | | | | | | |
| Barge | VPA | 4% | 4% | 4% | 4% | 4% | 3% | 3% | 3% | 3% | 4% | 4% | 4% | 4% | ↑↑ |
| Rail | VPA | 28% | 30% | 32% | 34% | 33% | 33% | 37% | 35% | 35% | 34% | 32% | 33% | 32% | ↑↑ |
| Truck | VPA | 68% | 66% | 64% | 62% | 63% | 64% | 61% | 62% | 62% | 63% | 64% | 63% | 64% | ↓↓ |
| | | 100% | 100% | 100% | 100% | 100% | 100% | 101% | 100% | 100% | 100% | 100% | 100% | 100% | |
| Rail Mode Share (%), freight with HR origins, by value and tonnage | FAF | | | | | | | | | | | | | | |
| by tonnage ²⁶ | FAF | 35% | n.a. | 8% | n.a. | n.a. | 1.6% | n.a. | 4.1% | n.a. | n.a. | n.a. | n.a. | n.a. | ↑↑ |
| by value ²⁶ | FAF | 3% | n.a. | 14% | n.a. | n.a. | 1.2% | n.a. | 2.9% | n.a. | n.a. | n.a. | n.a. | n.a. | ↑↑ |
| Rail Mode Share (%), freight with HR destinations, by value and tonnage | FAF | | | | | | | | | | | | | | |
| by tonnage ²⁶ | FAF | 44% | n.a. | 61% | n.a. | n.a. | 48% | n.a. | 32% | n.a. | n.a. | n.a. | n.a. | n.a. | ↑↑ |
| by value ²⁶ | FAF | 5% | n.a. | 23% | n.a. | n.a. | 9% | n.a. | 5% | n.a. | n.a. | n.a. | n.a. | n.a. | ↑↑ |
| 10. per capita vehicle miles traveled | | | | | | | | | | | | | | | |
| Daily Vehicle Miles Traveled (VMT) per capita | VDOT | 23.8 | 23.6 | 23.1 | 22.7 | 22.3 | 22.7 | 23.3 | 23.4 | 23.3 | 23.8 | 20.8 | 21.6 | n.a. | ↓↑ |
| % of Commuters with Journey-to-Work by Alternate Modes ⁸ | Census | 19% | 19% | 19% | 18% | 18% | 18% | 20% | 19% | 19% | 19% | n.a. | 27% | n.a. | ↑↑ |
| 11. maintenance | | | | | | | | | | | | | | | |
| % of Pavement in Non-Deficient Condition, VDOT-maintained roads ²⁷ | VDOT | 66% | 76% | 75% | 83% | 85% | 89% | 93% | 93% | 93% | 90% | n.a. | n.a. | 82% | ↑↑ |
| % of Bridges Not Structurally Deficient | VDOT | 94% | 94% | 94% | 94% | 94% | 93% | 94% | 95% | 95% | 95% | 96% | 96% | 97% | ↑↑ |
| Total Transit Revenue Service Interruptions (mechanical) per million PMT | FTA ⁶ | 45 | 38 | 29 | 27 | 32 | 58 | 46 | 34 | 41 | 41 | 41 | 60 | n.a. | ↓↑ |
| B. Financial System Performance Measures | | | | | | | | | | | | | | | |
| Actual Obligations / Planned Obligations ¹¹ | VDOT | n.a. | n.a. | 1.28 | 0.95 | 1.14 | 0.60 | 0.53 | 0.72 | 0.60 | 0.65 | 0.94 | 0.85 | 1.45 | n.a. |
| Average Age of Federal Dollars Spent on TIP Projects ¹⁴ | VDOT | n.a. | ↓↑ |
| Mid-Fiscal-Year Total of Unspent Obligations for TIP Projects ¹² | VDOT | n.a. | ↓↑ |
| % of Total District Allocn's in SYIP (i.e. omitting St'wide ³¹), year one ⁴ | VDOT | | | | | | | | | | | | | | |
| Bristol HRTPO Calculatior | | 8% | 10% | 10% | 11% | 8% | 5% | 5% | 6% | 3% | 4% | 4% | 7% | 5% | n.a. |
| Culpeper HRTPO Calculatior | | 3% | 2% | 3% | 8% | 5% | 3% | 4% | 4% | 3% | 3% | 1% | 3% | 3% | n.a. |
| Fredericksburg HRTPO Calculatior | | 4% | 3% | 6% | 5% | 4% | 6% | 7% | 9% | 4% | 4% | 7% | 6% | 11% | n.a. |
| Hampton Roads HRTPO Calculatior | | 13% | 16% | 21% | 29% | 28% | 36% | 34% | 27% | 22% | 31% | 27% | 29% | 34% | ↑↑ |
| Lynchburg HRTPO Calculatior | | 3% | 2% | 2% | 2% | 1% | 2% | 4% | 5% | 3% | 3% | 2% | 3% | 3% | n.a. |
| Northern VA HRTPO Calculatior | | 46% | 51% | 37% | 25% | 31% | 26% | 27% | 22% | 49% | 38% | 44% | 25% | 25% | n.a. |
| Richmond HRTPO Calculatior | | 11% | 8% | 8% | 8% | 7% | 9% | 10% | 11% | 9% | 7% | 4% | 9% | 9% | n.a. |
| Salem HRTPO Calculatior | | 7% | 3% | 7% | 8% | 8% | 6% | 6% | 8% | 5% | 6% | 8% | 12% | 5% | n.a. |
| Staunton HRTPO Calculatior | | 6% | 5% | 6% | 4% | 7% | 6% | 4% | 7% | 3% | 4% | 2% | 5% | 5% | n.a. |
| total | | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% | 100% | |

See page 51 for an explanation of footnotes.

STATE PERFORMANCE MEASURES

Footnotes

1 Transportation Analysis Zone (TAZ) data from regional 4-step model

2 Data employment by job location as "jobs" measure; employment by home location as "labor force" measure

3 Calculated via equation 2 in "Feasibility of Using Jobs/Housing Balance in Virginia Statewide Planning", VTRC, Aug 2010, pg. 26; 0: perfectly balanced; 1: perfectly unbalanced.

4 First fiscal year shown in SYIP, e.g. the "2013" number shown herein comes from the FY13 column of the FY13-18 SYIP.

5 New performance measure for FY13 evaluation (i.e. not included in FY12 evaluation).

6 FTA's National Transit Database

7 These two pollutants (NOx and VOC)--precursors of ground-level ozone--are measured in several Va. MPOs for AQ conformity.

Note: "2011" numbers are from VDOT's MOBILE 6.2 model; subsequent numbers will be calculated using MOVES model, making comparison to earlier numbers difficult.

8 Sum of all modes other than Drove Alone (i.e. including bike, ped, transit, work-at-home, carpool, etc.).

9 Given the necessary proximity of jobs to houses of persons who walk to work, this measure is intended to cover both job and housing access to pedestrian facilities.

10 The goal of HOV lanes--carpooling--is measured herein.

11 Actual obligations ("Obligated") / planned obligations ("TIP"); source: Annual Obligation Report (AOR).

12 "Total" = "Unspent Obligations" for each project, summed over all projects in TIP.

Due to large amount of funds typically obligated near end of fiscal years, "Total" calculated via financial "snapshot" taken near middle of subject fiscal year.

"Unspent Obligations" for a project = (total obligations for any year up to and including FY of snapshot) - (total spent in any year up to snapshot date).

Because the "total obligations" will exclude matching funds, the "total spent" should exclude matching funds.

13 The source of the first ten category names is Section 33.1-23.03 Code of Va. [amended via Chapter 670],

except that "movement of freight" is used herein instead of original "movement of freight by rail"; category 11 and financial RPMs were added by HRTPO.

14 This calculation covers all federal transportation dollars spent during the subject fiscal year.

"Average Age" is a weighted average of the ages of each payment made during the subject fiscal year.

The age of a specific payment is calculated by comparing the date of the payment to the date of the appropriate obligation for that payment.

To calculate "Average Age", weight the age of each payment by the amount of that payment.

If the actual dates are not available, monthly or FY data may be used, e.g. the age of a payment made in FY11 for an obligation made in FY09 is 2.0 years.

15 For air quality conformity, VDOT estimates emissions for various future years including one near future year; NOx and VOC emissions for the ozone season, and CO2 emissions as annual averages.

16 In addition to the pollutants required for AQ conformity, VDOT calculates CO2 when it conducts analyses for conformity.

17 Due to slow release of TAZ data by the CTPP, in later years staff used ACS data by Block Group (block groups being similar in size to TAZs).

18 Due to the relatively large size of a typical TAZ, consider only those TAZs which are bordered or penetrated by transit as being served by transit.

19 FTA's "National Transit Database" uses the term "collisions" ("Collision_Total"), instead of "crashes".

20 FRA uses the term "accidents".

21 Using July estimates from Weldon Cooper for nine localities (Ches., Norf., Ports., Suf., VaB., Hamp., JCC, NN, Wlmbg.).

Note: The Urbanized Area (UZA) population (which is typically used by FTA) could not be found for inter-census years.

For year 2000, the HR9 Weldon Cooper population (1,413,272) is similar to the Urbanized Area (UZA) population (1,394,439).

22 "Fatalities"= number of people died; "Accidents"=number of crash events; NTSB and FAA use the term "accidents".

23 No rate (e.g. "per PMT") is included here because the number of person-miles-of-travel (PMT) in the airspace above Hampton Roads is not known.

24 "DMV": Department of Motor Vehicles.

25 Rate shown is for a 3-year period ending in year shown.

26 Including domestic portion of international freight movement.

27 VDOT-maintained roadways only.

28 VMT for this year not yet available.

29 PMT for this year not yet available.

30 OCR = "Total Costs excl. OPEB's, Capital Charge and Other Costs" / "Total Revenue". (OPEB: other post-employment benefits)

31 Note: Some large projects (e.g. US 460, I-95 HOT Lanes) are in "Statewide".

32 Note: Norfolk Amtrak began on 12-12-12.

33 CTPP: Census Transportation Planning Products; ACS: American Community Survey

34 VWC: Virginia Workforce Connection